

SAFE WORK METHOD STATEMENT

Riskify Professional
Builder

PROJECT DETAILS

Project: Sydney Highrise Construction SWMS
Location: 456 Collins Street, Sydney NSW 2000
Contractor: Elite Construction Group
Job Number: SYD-2025-003
Trade: High Rise Construction
Date: 16/06/2025

RISK RATING LEGEND

LOW	Continue with current controls
MEDIUM	Additional controls may be required
HIGH	Additional controls required
EXTREME	Stop work - eliminate/substitute

Activity/Task	Hazards Identified	Risk Level	Control Measures	Legislation/Standards	Responsible Person
Site Establishment & Access Control	Manual handling, Trip hazards, Vehicle movement, Confined spaces	MEDIUM	Use mechanical aids, Clear walkways, Traffic management plan, PPE required, Confined space entry permits		Site Supervisor
Excavation & Foundation Works	Cave-in, Underground services, Machinery operation, Ground collapse	MEDIUM	Dial before you dig, Trench shoring systems, Exclusion zones, Competent operator certification, Ground stability assessment		Site Supervisor
High Rise Construction	Falls from height, Falling objects, Electrical hazards, Weather exposure	MEDIUM	Fall protection systems, Safety barriers, Hard hats, Lockout/tagout procedures, Weather monitoring protocols		Site Supervisor
Crane & Lifting Operations	Crushing, Structural failure, Load displacement, Overhead hazards	MEDIUM	Licensed crane operators, Pre-lift inspections, Load charts compliance, Exclusion zones, Spotters		Site Supervisor

EMERGENCY PROCEDURES

- Emergency Services: 000
- Site Supervisor Contact: Available during work hours
- Evacuation Assembly Point: As per site emergency plan
- First Aid Officer: Trained personnel on site

- Incident Reporting: Immediate notification to supervisor

- Emergency Equipment: First aid kit, fire extinguisher locations marked

