

SAFE WORK METHOD STATEMENT

Project: High-Rise Electrical Installation - Southbank Tower Location: 456 Southbank Boulevard, Southbank VIC 3006

Document ID: SWMS-141-13844

Date: 19/06/2025

PROJECT INFORMATION

Principal Contractor: Elite Construction Management

Project Name: High-Rise Electrical Installation - Southbank Tower

Project Address: 456 Southbank Boulevard, Southbank VIC 3006

Trade Type: Construction

Document Version: 1.0

EMERGENCY PROCEDURES

Emergency Contact: 000

Assembly Point: Main Gate Assembly Area

Nearest Hospital: Royal Melbourne Hospital

 Site Supervisor:
 0412 345 678

 First Aid Officer:
 0423 456 789

CONSTRUCTION CONTROL RISK MATRIX

A - QUALITATIVE SCALE

Extreme Fatality, significant disability

High Minor amputation, permanent disability

Medium Minor injury, Lost Time Injury

Low First Aid Treatment only

C - LIKELIHOOD vs CONSEQUENCE



B - QUANTITATIVE SCALE

\$50,000+ Likely - Monthly

\$15,000-\$50,000 Possible - Yearly

\$1,000-\$15,000 Unlikely - 10 years

\$0-\$1,000 Very Rarely - Lifetime

D-RISK SCORING

16-18 Severe (E) Action now
11-15 High (H) Action 24hrs
7-10 Medium (M) Action 1 week
1-6 Low (L) Monitor

WORK ACTIVITIES & RISK ASSESSMENT

Activity	Hazards	Initial Risk	Control Measures	Residual Risk	Legislation
Cable tray installation on levels 15-20	Falls from height during work activities Manual handling of heavy cable trays Electrical hazards from live circuits	H (16)	Safety harness with dual lanyards required Use mechanical lifting aids Lockout/tagout procedures before work	L (4)	WHS Regulation 2017 Part 4.4 - Falls, AS/NZS 3000:2018
Main switchboard upgrades	Electrical shock from live components Manual handling injuries from heavy equipment Arc flash potential	H (15)	 De-energize circuits before work Use insulated tools and PPE Mechanical lifting aids for panels 	L (3)	AS/NZS 3000:2018 Wiring Rules, AS/NZS 4871.1-2015
Lighting circuit installation	 Falls from height using ladders Electrical shock hazards Eye strain from poor lighting 	M (12)	 Scaffold access platforms Test circuits before touching Adequate temporary lighting 	L (2)	AS/NZS 3000:2018 Section 2, AS 2293.1-2018
Emergency lighting system testing	Working in low light conditions Electrical testing hazards Falls during emergency testing	M (9)	 Portable lighting during tests Qualified electrical testing personnel Fall protection systems 	L (2)	AS 2293.1-2018 Emergency Lighting, WHS Regulation 2017
Final electrical testing and commissioning	Electrical shock during testing Equipment malfunction Documentation errors	M (8)	Qualified electrical engineers Proper testing equipment Systematic testing procedures	L (2)	AS/NZS 3017:2022 Electrical Installations, AS/NZS 3760:2022

PLANT & EQUIPMENT REGISTER

Mobile Scaffold

Inspection: Daily visual check

Status: Current

Power Tools

Inspection: Pre-use inspection

Status: Tagged & Tested

Electrical Testing Equipment

Inspection: Calibration check

Status: Certified

Lifting Equipment

Inspection: Weekly inspection

Status: Load tested

EMERGENCY RESPONSE PROCEDURES

FIRE

Evacuate immediately, call 000, assemble at designated point

INJURY

Provide first aid, call 000 if serious, notify supervisor

EVACUATION

Follow evacuation routes, proceed to assembly point

SPILI

Contain spill, notify environmental officer, clean up

SAFETY SIGNAGE & COMMUNICATION

- 1. Danger High Voltage signs at all electrical work areas
- 2. PPE Required signs at site entrances and work zones
- 3. First Aid and Emergency Assembly Point signage clearly visible
- 4. Hazard identification signs for specific work area risks
- 5. Tool box talk records and safety briefing documentation
- 6. Site safety rules and emergency contact information displayed

